



International
Centre for
Radio
Astronomy
Research

Extension and upgrade of the Murchison Widefield Array: Introduction and context



Credit: Natasha Hurley-Walker

Prof. Steven Tingay

MWA Director, ICRAR – Curtin University

On behalf of the international MWA consortium



Australian Government




Meeting sponsors:

AAL administers MWA funding

CAASTRO a primary science user - 45% of integrated MWA science output thus far led by CAASTRO staff/students.



Astronomy
Australia
Ltd.



CAASTRO
ALL-SKY ASTROPHYSICS



<http://www.mwatelescope.org>

<http://www.facebook.com/Murchison.Widefield.Array>


Antennas



Receivers



Central Signal Processing



800 km of optical fibre



Pawsey Centre





Murchison Shire Boundary

MRO (operated by CSIRO)

On site: data rate into central building ~60 Gbps

41,000 sq. km = The Netherlands

Population density = 0.002 people/sq. km

Geraldton

Off site: data rate into science archive ~3 Gbps

~200 km

Perth



Pawsey Centre 9 PB storage for MWA archive = 2 years of operation

Tingay et al. 2013, PASA, 30, 7
(MWA system description paper)

- 128 tiles;
- 3 km maximum baseline;
- Configuration balanced between short baselines for EoR and longer baselines for surveys/solar;
- 80 – 300 MHz frequency range;
- 30 MHz processed bandwidth.

Bowman et a. 2013, PASA, 30, 31
(MWA science description paper)

Overall extension plan

Extension and upgrade of the MWA in two phases:


- Phase 1:
 - additional 128 tiles added to the array, split between additional short baselines and new longer baselines;
 - Maximum baseline ~doubled to ~6km;
 - Periodically reconfigure to correlate 128 out of 256 tiles at a time;
 - Lower bottom edge frequency to ~50 MHz?

- Phase 2:
 - Correlate all 256 tiles;
 - Entirely new analog/digital signal path: beamformers (high performance analog or digital?); receivers (PFBs); correlator; imaging/calibration pipeline (RTS+); data archive;
 - Even more tiles (longer baselines??), full bandwidth, 50 MHz bottom frequency, higher spectral/time resolution, higher performance and more stable signal path.


Boundary conditions

- Phases 1 and 2 both give excellent improvements in science capability;
- Phase 1 allows for a smooth continuation of the existing operations model, existing signal path, and existing software systems ;
- Phase 1 recognises constraints in geography/heritage/power at the MRO, as well as compatibility with the existing signal path (type and amount);
- Phase 1 low risk/development, high science return, rapid deployment, low cost – lays base for more ambitious Phase 2;
- Phase 2 requires longer lead time, more development. Reduce cost and risk by undertaking systematic and early development to produce detailed project plan.
- Managed/financed centrally as two separate projects:
 - Minimise risk;
 - Minimise cost.

Phase 1



New tiles serviced by RFoF (RF over fibre): David Emrich.




New tiles serviced by independent power systems (solar/batteries)

Existing tiles, beamformers, receivers.

New RFoF interfaces at beamformer and receiver ends.

Heavily leverages excellent federally-funded SKA pre-con work at ICRAR.



Phase 2

- Replace the entire analog/digital signal path:
 - LNA/ASC modifications to go lower in frequency, to ~50 MHz (could also possibly be considered for Phase 1);
 - New beamformers (analog or digital?) for finer pointing control and improved calibration transfer;
 - New receivers (sampler/digitiser/PFB) for wider bandwidth, smoother frequency response, reduced aliasing; higher frequency resolution;
 - New correlator for wider bandwidth, non-zenith correlation (to accommodate longer baselines), higher time/frequency resolution;
 - New voltage capture modes?
- The addition of even more tiles for even longer baselines?

Going lower in frequency

75 MHz

Potential
after mods.

Existing
system



Cost/schedule

Primary Column	2014				2015				2016				2017				2018				2019				2020				2021				2022							
	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4				
Current operations																																								
Meeting preparation (design/cost)																																								
Phase 1 preliminary design																																								
Secure Phase 1 funding (ARC LIEF)																																								
Phase 1 procurement																																								
Phase 1 deployment (incl.co)																																								
Phase 1 operations																																								
Phase 2 preliminary design																																								
Secure Phase 2 funding																																								
Phase 2 procurement																																								
Phase 2 deployment (incl. cc)																																								
Phase 2 operations																																								

David Emrich design/cost spreadsheet for Phase 1 construction ~ \$2.9m
 Tom Booter advises we carry 30% contingency at this point in the design process.

Phase 1 budget: ARC LIEF + partner contributions (thoughts welcome on alternatives)

Phase 2 budget: NCRIS or replacement?

Operations budgets: NCRIS/partner contributions?

Budget (Phase 1)

- Currently MWA has 13 institutional partners in four countries;
- Assume some new partners and not all existing partners (new partners pay premium to join project after the initial large investment of existing partners);

$$T_n = T / (n_e(1 - d) + n_n); T_e = T_n(1 - d)$$

T = Total cost;

T_e = Existing partner contribution

T_n = New partner contribution

n_e = Number of existing partners

n_n = Number of new partners

d = Discount factor for existing partners

$$T = \$2.9m$$

$$T_e = \$300k$$

$$T_n = \$370k$$

$$n_e = 6$$

$$n_n = 3$$

$$d = 0.2$$

ARC LIEF (cash)

Curtin: \$100k

Five AU partners: \$30k

ARC request: ~\$1.5m

Three non-AU partners: \$400k

\$3m (no contingency)

Questions for this meeting

- Comments on the overall Phase 1/2 concept;
- What split of additional tiles between core (EoR) and long baselines (GLEAM++/solar) in Phase 1?;
- Which sets of 128 tiles constitute useful arrays in Phase 1 (could possibly have more than two combinations)?;
- What duty cycle of re-configuration between EoR and survey arrays in Phase 1?;
- Lower frequency from 80 MHz to 50 MHz in Phase 1 or 2?;
- Any other capabilities worth thinking about for Phase 2? Additional tiles?;
- What duration for operations phases?;
- Is your institution (new or existing) interested in joining a re-formed MWA consortium to participate in this plan, contribute to a LIEF proposal for the next round?;
- Any other questions to consider?

Final comments

- MWA has been one of the success stories of last decade. Just hitting its stride in science productivity: 17 papers published; 13 in collaboration/journal review; and 19 in preparation;
- Strong support in current Decadal Plan preparation for MWA extension/upgrade;
- MWA extension appears highly relevant for CAASTRO renewal;
- CAASTRO and the MWA is a powerful combination for science (people + infrastructure);
- Excellent new science capabilities for a reasonable amount of money;
- Importantly, bridge the gap to SKA-low. Continue to build advanced Australian capabilities for the SKA era.

THANKS!!!

Wadjjarri Yamatji
people

Traditional Owners
of the MRO site



CSIRO

Operates the MRO



Astronomy Australia
Limited

Administers
Federal funding



Australian
Government

Provides
Federal funding



Western Australian
Government

Provides
State funding



CAASTRO

Major science partner

